


The PHENIX Multiplicity and Vertex Detector

Michael Bennett
Los Alamos National Lab

1. Overview
2. Design Challenges
3. Performance
4. Status



MVD Overview:

Physics goals:

Charged particle multiplicity

Centrality trigger at LVL-1

Collision vertex position (< 2 mm)

dN/d d^2N/d d

Design Challenges:

Large acceptance ($= 5$, full)

High granularity (large track density)

Minimal material in electron arm acceptance

Compact Read-out electronics

The Multiplicity Vertex Detector


Clamshell design - mounts to magnet pole faces.

Inner and outer barrels of silicon strip detectors, 200 μ m, 64cm length

Silicon pad endcaps @ +/- 35cm

Rad length \approx 1.1%


Weight < 30lb



Strip electronics at bottom - Multichip Module
256 channels/detector
Channel count = 34,816





Double Metal Pad Detector



- *Eliminates specialized kapton cable
- *Reduces wirebonding
- *Facilitates detector probing
- *Facilitates assembly, handling

Front End Electronics:



Final MCM:

Design at LANL/NIS

Lead Engineer - Gary Smith

Lead Designer - Gary Richardson

| | | |
|--------|--------------|---------------|
| 1 MCM: | 256 channels | 2 Xilinx 4010 |
| | 8 preamps | 1 opamp |
| | 8 AMUADCs | 1 Temp sensor |

Trace pitch = 54 μm

Line width = 43 μm

I/O pad pitch = 150 μm

I/O pads gold sputtered for wire bonding

base metal + 4 trace layers = Ti - Cu - Ti


M1 = signals, all connections off IC chips

M2 = bus lines


M3 = power lines

M4 = surface mount components


The pseudo-tracking algorithm:




The correlation algorithm:







offset + outer silicon hits scaled by $\frac{R1}{R2}$



offset scaled by $\frac{R2}{R1}$ = vertex position



MVD vertex finding resolution



MVD Construction Status:

All mechanical and electrical components prototyped or in fabrication.

Si pad detectors starting production.

Si microstrip detectors in production.

Rohacell C-cages in production at UCR.

All custom die are manufactured - KGD testing.

MCMs delivered by Lockheed-Martin in mid-summer.

All custom electronics boards are in fabrication.

All kapton cables are in production.

Cooling system components being procured.

Construction Complete at LANL in spring of '99.

Installation in PHENIX in June '99.

First heavy-ion beam in Oct. '99.